



- A. DIMENSIONS ON FLOOR PLAN ARE BASED ON FACE OF FINISHED WALL TO FACE OF FINISHED WALL (NOMINAL).
- B. VERIFY ALL DIMENSIONS AND CONDITIONS AT JOB SITE. PORTIONS OF EXISTING CONSTRUCTION MAY HAVE BEEN REMOVED BY OWNER.
- C. MAINTAIN CONTINUOUS UTILITY SERVICE TO ALL SPACES IN THE BUILDING NOT AFFECTED BY THIS WORK. COORDINATE WITH OWNER ANY DISRUPTION IN SERVICES REQUIRED TO PERFORM WORK OR TO MODIFY EXISTING PIPING, DUCTWORK OR ANY ASSOCIATED EQUIPMENT.
- D. REFER TO SHEET 830 FOR ROOF FINISH & MATERIAL SCHEDULE AND NOTES.
- E. REFER TO SHEET 830 FOR DOOR SCHEDULES, DOOR TYPES, AND NOTES.

- ① PATCH DOOR & FRAME FINISHES TO MATCH EXTG DUE TO DOOR HARDWARE REMOVAL
- ② PATCH EXTG WALL FINISH DUE TO DOOR HARDWARE & HAND READER REMOVAL
- ③ VERIFY LOCATION OF NEW PUSH PADS WITH OWNER PRIOR TO ROUGH-IN
- ④ NEW FIRE STROBE LOCATION
- ⑤ UPGRADE EXTG PARTITION CONSTRUCTION TO 1 HR FIRE RESISTANCE RATING. PATCH EXTG PARTITION PENETRATIONS WITH GYPSUM BOARD OR FIRE SAFING SEALANT. STENCIL NEW PARTITION RATING ON BOTH SIDES OF PARTITION ABOVE CEILING
- ⑥ EXTG HANDREADER LOCATION, REWIRE TO PROVIDE ACCESS TO ELEVATOR IT AND DOOR 0-546.
- ⑦ NEW DATA OUTLETS, CONDUIT & WALL BOXES BY OWNER
- ⑧ NOT USED
- ⑨ RELOCATED HAND READER, LOCATE FALM SENSOR AT 44" AFF
- ⑩ PROVIDE NEW SMOKE DETECTOR FOR DOOR 0-546. LOCATE WITHIN 1'-0" OF DOOR IN HIGH GYP BOARD CEILING

PARTIAL LEVEL 0 FLOOR PLAN